

Mercer and Miller

M&M

26-28, Hammersmith Grove
LONDON W6 7BA

ITEM	DESCRIPTION			RATE £	TOTAL £	ELEMENT TOTAL £
	<u>DIVERSION OF 150MM UNDERGROUND FOUL SEWER</u>					
	Drawings from Martin J Harvey show the diversion of an existing live 150mm sewer to be diverted through the site					
1.00	Initial Southern Water design and approval process		1 item	£1,000.00	£1,000.00	
2.00	Allow for traffic management for works in the public Highway		1 item	NIL		£1,000.00
3.00	Excavate down to expose the existing foul drain on site - assume at 2m deep maximum		1 location	£1,500.00	£1,500.00	
4.00	Excavate in the Highway for the full length of the diversion 2m deep including new 150mm pipe and concrete surround and backfilling with new pea shingle to underside of subbase	NIL	m	£220.00		
5.00	Ditto on site		27 m	£155.00	£4,185.00	
6.00	New manholes		3 Nr	£1,500.00	£4,500.00	£10,185.00
7.00	Reinstatement of highway surfacing		35 m2	NIL		
8.00	Tanker cost for temporary flow of foul waste		2 Nr	£750.00	£1,500.00	£1,500.00
9.00	Southern Water sign off and licence fees		1 item	£1,000.00	£1,000.00	£1,000.00
					£13,685.00	£13,685.00
	Add Prelims and Management		15%		£2,052.75	£2,052.75
					£15,737.75	£15,737.75
	Excludes fees					